


INSTALLATION INSTRUCTIONS

1. ENSURE THE APERTURE IS CLEAN AND FREE OF DUST AND DEBRIS.
2. APPLY RYANFIRE MASTIC INTO THE ANNULAR GAP BETWEEN THE SPRINKLER HEAD / STEEL PIPE AND THE KOROK® PANEL, TO THE FULL DEPTH OF THE PANEL.
3. CLEAN ANY EXCESS SEALANT WITH A DAMP CLOTH.



Products: RYANFIRE MASTIC
Approvals: AS 1530.4:2014/AS 4072.1:2005
BK: 276
Ref: 23SFR00058
ID: I

Scenario: Penetration seal to sprinkler pipe & sprinkler head

Services: Up to Ø28mm steel pipes & sprinkler heads

Annular: 6 - 8mm
Construction: 78mm KOROK® (non trafficable) ceiling

Fire Integrity: 120 minutes
Fire Insulation: 0 minutes

Web based drawings are for example only. Fire performance of any system is dependant on, but not limited to size of opening, substrate, if penetrations are passing through, type, size and number. Please refer to Ryanfire technical department for detailed and specific fire performance information.



RYANFIRE Technical Support:
info@ryanfire.co.nz - Tel 09 443 0362

Drawing Title
**Ryanfire Mastic to sprinkler heads
78mm KOROK® panel ceiling**

Scale NTS	Date April 2025
Drawing Number V2.1	Rev 3.0

All errors and omissions excepted. The information contained within this drawing is believed to be correct on the date of publication, and is based upon tested and certified solutions. The policy of **Ryanfire Products** is one of constant improvement. Installers must ensure that they are following the latest published drawings, test evidence and instructions. Whilst **Ryanfire Products** will endeavour to keep its publications up to date, the accuracy of the information contained within this drawing may be affected by pertinent changes in the law or regulatory requirements and alterations or amendments to the specification of the **manufactured** products. Terms and conditions of sale apply.

Ryanfire Products owns and has copyright to these drawings. They are to be used only for the purpose for which they were intended and supplied and are not to be sold, transferred or made available for use by a third party. Any misuse of these drawings will result in legal proceedings.